# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

**Executive Engineeer**
**Byatarayanapura Division**
**B.B.M.P., Bangalore - 92**

## APPROVED SCHEDULE - B

**Issued to :** **Original / Duplicate**

**Name of the Work : Improvements and Asphalting to HMT Layout Balance Roads in ward No. 09 of Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description | Unit | KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 483.80 | Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work | Cum | 90.72 | Rupees Ninety and Seventy Two Paise Only |
| 2 | 825.00 | Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work | Sqm | 50.11 | Rupees Fifty and Eleven Paise Only |
| 3 | 825.00 | Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work | Sqm | 70.04 | Rupees Seventy and Four Paise Only |
| 4 | 3185.00 | Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work | Sqm | 40.50 | Rupees Forty and Fifty Paise Only |
| 5 | 477.75 | Providing, laying, spreading and compacting graded stone aggregate to **wet mix macadam** specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work | Cum | 1121.04 | Rupees One Thousand One Hundred Twenty One and Four Paise Only |
| 6 | 3185.00 | Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work | Sqm | 10.53 | Rupees Ten and Fifty Three Paise Only |
| 7 | 3185.00 | Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work | Sqm | 44.28 | Rupees Forty Four and Twenty Eight Paise Only |

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Signature of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore



Executive Engineer

| Sl. No. | Approved Qty. | Description | Unit | KRIDL | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 8 | 79.63 | Providing and laying **semi dense bituminous concrete** 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. **With 80/100 grade bitumen,** etc complete as per specifications and directions of engineer in charge of the work | Cum | 9631.44 | Rupees Nine Thousand Six Hundred Thirty One and Forty Four Paise Only |
| 9 | 483.80 | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work | Cum | 72.71 | Rupees Seventy Two and Seventy One Paise Only |

**I am prepared to execute the above mentioned work written by me in Schedule - B**

**Contractor Signature**
**Reg. No.**
**Postal Address**

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL, BBMP, Bangalore

**Executive Engineer**
**Byatarayanapura Division**
**BBMP, Bangalore - 92**